


**NOTES:**

- 1 Anchors shall be installed according to manufacturer's specifications.
- 2 Frame shall be welded to the steel pipes all around.
- A All steel pipe shall be according to ASTM A500, Grade C.
- B Welding shall be according to CSA W59.
- C All parts shall be hot dipped galvanized according to ASTM A123 after fabrication.
- D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev 2	
<b>SPLASH GUARD, PEDESTRIAN INSTALLATION</b>	-----	-----	
<b>OPSD 982.101</b>			