


NOTES:

- 1 One 25mm diameter rigid PVC conduit required for each signal head. Install all signal heads prior to installing conduit. Install conduit system to obtain a neat and straight installation.
 - 2 On concrete poles, mount conduits using 16mm stainless steel strapping and buckles. On wooden poles, mount conduits using PVC coated steel or galvanized pipe straps with 6x38mm lag screws.
- A For orientation and location of poles and equipment refer to layout drawings.
 B All dimensions are in millimetres unless otherwise shown.

<p>ONTARIO PROVINCIAL STANDARD DRAWING</p>	<p>Nov 2019</p>	<p>Rev 3</p>	
<p>TRAFFIC SIGNAL SYSTEM EQUIPMENT ON WOODEN OR CONCRETE POLES OVERHEAD WIRING INSTALLATION</p>	<p>OPSD 2552.010</p>		